

BILL No. 1: PRELIMINARY AND GENERAL ITEMS					
ITEM	BRIEF DESCRIPTION	UNIT	QTY	RATE	AMOUNT
				(KES)	(KES)
	<i>Preliminary and General Items are subject to the Conditions of Contract and the Specifications of the Contract.</i>				
	<u>Contractual Requirements</u>				
1	Performance Security, according to Clause 55 of GCC.	Item	1		
2	Insurance for loss of or damage to the works, plant, and materials, according to Clause 14 (a) of GCC.	Item	1		
	<u>Performance Requirements</u>				
3	Mobilization and maintenance of Contractor's plant and equipment for the Contract period, including demobilization when finishing the Contract, as Lump Sum.	Sum	1		
					0
4	Fabrication and erection of Project Sign Boards, according to the Specifications.	Nr.	1		
					0
5	Allow for testing associated with Earthworks and Concrete Works, as required by the Project Manager, as Lump Sum.	Sum	1		
					0

6	Constructions of Contractor's camp and office	Sum	1		
					0
7	Allow for PC sum of Ksh.300,000 for supervision by CWSB staff		1	300,000	300000
					0
8	Allow for overheads and profits on item 10	%	0.1	300000	30000
					0
9	Total of Bill 1 Page 1 Carried to Collection Page				

BILL No. 1: PRELIMINARY AND GENERAL ITEMS					
ITEM	BRIEF DESCRIPTION	UNIT	QTY	RATE	AMOUNT
				(KES)	(KES)
10.	<p>The contractor shall set out below and fully describe and price, in the spaces provided, any or temporary work or obligation or anything in the Conditions of Contract or in the Specification not included by him in his rates elsewhere and for which he considers a separate charge is required. The prices inserted shall be considered to be fixed lump sums covering the whole of the work and as such will not be subjected to adjustment for any reason. If the Contractor makes no entry in the space provided then the rates inserted elsewhere in the Bill will be deemed to cover all his obligations under the Contract.</p> <p>i)</p> <p>ii)</p> <p>iii)</p> <p>iv)</p>				
Total of Page Bill 1. Carried to Collection Page					

BILL No.2: SITE CLEARANCE, DESILTING AND DREDGING

ITEM	DESCRIPTION	UNIT	QTY	RATE (KSHS)	AMOUNT (KSHS)
2.1	Site clearing and soil stripping: Clear the site of trees/bushes/stumps and top soil including soil stripping (to depth of 200mm) and cart away to spoil as directed by the Engineer. The dimensions of the area to be cleared 1,000m ²	M ²	1,000		
2.2	Allow for preparation of site access road for plant and equipment	Sum	1		
2.3	Allow for maintenance of site access road above	SUM	1		
2.4	Excavate in soft rock for cut-off trenches as advised by the Supervisor	m ³	2		
					-
2.5	Place approved Reinforced Concrete 1:2:4 in a 30m long; 2.50m wide and 5.0m high retaining wall for Cross Weir.	m ³	400		
TOTAL BILL NO. 2 carried to SUMMARY PAGE					

Bill No	SUMMARY	COST IN KSH.
1	PRELIMINARY & GENERAL ITEMS	
2	SITE CLEARANCE, DESILTING AND DREDGING WORKS	
	TOTAL	
	Add 2 % Contingency	
	Add 16%VAT	
	GRAND TOTAL	
Bidder's Name:		
Bidder's Signature / Stamp:		
Date:		